BID #: DDD-2026/0811R1 **August 11th, 2026**

DEMOLITION PROPOSAL

PROJECT NAME:	Harbor Freight Tools, Jacksonville, Florida
PROJECT TYPE:	Open Shop
SCOPE:	DEMOLITION
ADDRESS:	14333 Beach Blvd, Jacksonville, Florida 32250

OUR SCOPE OF WORK

Disassemble Dynamics hereby proposes and agrees to furnish all necessary labor, material, machinery, equipment, tools, safety gear and supervision required to perform the following scope of work:

INCLUSIONS

- Remove fixtures, fixed or free-standing, throughout the space (Note 202)
- Remove all abandoned equipment in HFT space (Note 203)
- Remove abandoned electrical equipment not to be re-used, including junction boxes, conduit, and wiring (Note 205)
- Remove doors and frames complete where shown dashed (Note 208)
- Remove existing gyp. bd. wall and associated furring (Note 209)
- Remove lay-in ceiling completely, including all mechanical devices, diffusers, return air grilles, and lighting fixtures (Note 210)
- Remove light fixtures completely throughout HFT space (Note 212)
- Remove all existing floor finishes (Note 215)
- Cut out all remaining outlets, drains, and holes in the floor completely (Note 216)
- Remove existing storefront doors, storefront system, and portion of masonry wall (Note 219)
- Remove existing storefront door (Note 237)
- Remove existing hollow metal doors and frames completely (Notes 221, 227)
- Remove existing double doors and portion of existing interior masonry wall (Note 238)
- Remove existing O.H. door completely (Note 240)
- Remove existing signage, typical; coordinate with landlord as required (Note 223)
- Remove existing canopy and all associated attachments (Note 226)
- Remove existing canopy lighting completely (Note 236)
- Remove existing metal stair, rail, and all associated attachments completely (Note 230)
- Remove existing downspout (Note 231)
- Remove existing bollard (Note 233)
- Remove existing dock bumpers and seals completely (Note 235)
- Provide daily clean up of debris generated by demolition activities.

- Removal and disposal of all construction debris (C&D) created from this work to an approved landfill accepting this debris per city, county & federal codes & EPA regulations.
- All work conforms to state and local code requirements.

EXCLUSIONS

- Temporary power, temporary lighting, temporary water. Temporary site offices, temporary sanitary facilities.
- Barricade / temporary enclosures / temporary protection / dust barriers / road closures.
- Patching, repair work, welding, and refurbishing by others.
- Concrete pour back, in-fill.
- Roof demolition. Removal of main trunk lines and RTUs / AHUs.
- Remove furniture, equipment, safe, hood, appliances, workstations, and artwork.
- Shelving, fixtures, cabinetry, lockers, and such not shown in the drawings will be priced accordingly.
- Trash and/or debris left behind by previous tenant not shown in the drawings will be priced accordingly.
- Concrete x-ray / scanning by others. Markings & layouts by G.C.
- Asbestos abatement, asbestos survey, air monitoring, permit costs, sewer fee cost.
- Terminate cap & seal plumbing/sewer/gas lines. Electrical make safe.
- Core drilling, Saw-cut, trench & remove slab. Excavate dirt / soil. Shoring & bracing by G.C.
- Refrigerant to be drained by HVAC contractor prior to demolition.
- Grinding, sanding, bead blasting and/or using or removing chemicals/solvents/paints.
- Any element found above ceiling, under the flooring or behind walls not shown in the drawings will be subject to a change order.
- Utility work / disconnects / re-routes. Fire protection demolition & sprinkler work by others.
- Prepare shop drawings, rebar / bar-bending schedule, core samples, and mock-ups.
- This proposal excludes demolition/removal of hardwood flooring and ceramic tile.

SPECIAL NOTES

- Night work is not included in this offer.
- Proposal based on plans only, regardless of provided pictures.
- Disassemble Dynamic will be careful when performing the scope(s) of work listed above, however, is not responsible for any damages or disturbance to the ground, concrete slabs, sidewalks, foundations, irrigation, buildings, pavements, etc. caused by demolition & haul-off procedures.
- We acknowledge receipt of all addenda & supplemental notices for this project.
- Based on (1) mobilization. Disassemble Dynamic will charge $3,250.00 for every additional mobilization. This excludes the price of tools, machinery, and equipment.
- Disassemble Dynamic has the right to withdraw or modify this proposal, if not accepted in writing within 90 days of the above date.
- Disassemble Dynamic will charge for idle time lost. i.e., elevator malfunction, etc.
- Disassemble Dynamics will charge an additional amount if another disposal / waste management company is to be used. An allowance / change order will also be added if only 1 dumpster is allowed on the premises at a time or if the GC requires us to perform a ‘live load’.
- An allowance / change order will also be added if the dumpster location is farther than 150 yards from the building.
- Any other work requested shall be priced accordingly.

OUR OFFER

DESCRIPTION	USD
BASE BID	$ 44,950.00

3325 US-441 #101 • Lake City, FL, USA 32025 • Mob 386.365.7886 • E-Mail shawn@disassembledynamics.com

Alternate No. 1 — Grinding of concrete throughout existing space to leave a smooth and level surface ready to receive new flooring. (16,000 sqft)	$ 16,000.00
Alternate No. 2 - Remove existing concrete pads and portion of asphalt as required for new concrete pad and platform, forklift ramp, and egress stair (Note 224) Remove portion of asphalt as required for new concrete egress ramp (Note 225) Sawcut and remove portion of existing concrete walk and excavate as required for new concrete frost slab centered on door opening (Note 243)	$ 12,400.00
Alternate No. 3 - Remove portion of masonry wall for new bi-parting door package; shore as required; salvage brick as possible for future reuse (Note 234) Create a new opening in the masonry wall for 3'-0" x 7'-0" H.M. door and lintel; shore as required (Note 220) Create a new opening in the masonry wall for 8'-0" x 10'-0" O.H. door and lintel; shore as required (Note 239) Remove existing door and frame in masonry wall complete; expand opening for new 8'-0" x 8'-0" O.H. door and lintel; remove portion of masonry wall infill and existing dock equipment; shore as required (Note 218) Remove portions of existing interior masonry walls; cut masonry walls to two courses below slab (Notes 207, 238)	$31,100.00
Remove existing quarry tile, setting bed, and concrete slab in solid-hatched area, approx. 1,360 S.F. (Note 228) Sawcut and remove portion of existing concrete slab for plumbing trench, approx. 385 S.F. (Note 217)	$ 25,912.50
TOTAL	**$ 130,362.50**

PAYMENT TERMS

- Payment in full shall be made within thirty (30) days of completion.
- Taxes are not included in this proposal. Bonding is excluded.
- Quote is based on zero (0) retainage being withheld. All unpaid invoices shall carry interest in the rate of 2.5% per month until the balance is paid in full. In the event of any outstanding amount that must be collected by an attorney, the customer shall be liable for attorney's fees and costs of litigation. If payment is not received within 45 days from completion of job, a lien will be placed on the property.
- The party accepting this offer agrees that any dispute or conflict that arises from the contents of this bid, agreement or contract between the parties shall be heard in district court in Bexar County, Texas.

If you have any queries, please do not hesitate to contact the undersigned.

Best regards,

Shawn Ziegaus

3325 US-441 #101 • Lake City, FL, USA 32025 • Mob 386.365.7886 • E-Mail shawn@disassembledynamics.com