BID #: DDD-2026/0615R1 **June 15th, 2026**

DEMOLITION PROPOSAL

PROJECT NAME: Sunglass Hut, Naples, Florida
PROJECT TYPE: Open Shop
SCOPE: DEMOLITION
ADDRESS: 5414 Tamiami Trail N., Naples, FL 34108

OUR SCOPE OF WORK (INCLUSIONS)

Disassemble Dynamics hereby proposes and agrees to furnish all necessary labor, material, machinery, equipment, tools, safety gear and supervision required to perform the following scope of work:

- Remove and dispose of existing storefront glazing assembly and framing system in its entirety. (Keynote 2)
- Remove existing storefront signage and coordinate removal of associated electrical connections. (Keynote 3)
- Remove existing flooring and wall base down to the concrete slab. (Keynote 4)
- Remove existing door, frame, and hardware. (Keynote 7)
- Remove existing cashwrap, floor casework, furniture, and associated electrical and data hook-ups; remove wiring and conduit back to source. (Keynote 8)
- Remove existing partitions indicated for demolition and dispose of debris. (Keynote 10)
- Remove existing back-of-house shelving. (Keynote 11)
- Remove existing back-of-house furniture and equipment. (Keynote 12)
- Remove existing thermostat and associated controls as required; coordinate with mechanical drawings. (Keynote 13)
- Remove and dispose of existing exterior metal cladding at façade locations indicated. (Keynote 17)
- Remove and dispose of demolition debris generated by the work and leave areas broom clean upon completion.
- Remove and dispose of all existing ceiling-mounted items, including light fixtures, associated wiring, conduit, and related components back to source as required. Coordinate with mechanical and electrical drawings. (Keynote 1)
- Remove and dispose of existing ACT ceiling tile, ceiling grid, suspension system, and associated support components as indicated. (Keynote 2)
- Remove and dispose of existing traffic counter. (Keynote 5)
- Remove and dispose of existing speakers and associated wiring. (Keynote 6)
- Remove and dispose of existing exit light fixtures. (Keynote 7)
- Remove existing security cameras and retain for owner reuse or relocation as indicated. (Keynote 8)
- Remove and dispose of existing track lighting and associated components. (Keynote 10)
- Remove and dispose of existing storefront finishes designated for demolition. (Keynote 12)
- Demolish existing coved gypsum board ceiling in preparation for infill work. (Keynote 13)
- Remove existing HVAC diffuser grilles and retain for relocation by others in accordance with mechanical plans. (Keynote 14)
- Provide daily clean up of debris generated by demolition activities

- Removal and disposal of all construction debris (C&D) created from this work to an approved landfill accepting this debris per city, county & federal codes & EPA regulations.
- All work conforms to state and local code requirements.

EXCLUSIONS

- Temporary power, temporary lighting, temporary water. Temporary site offices, temporary sanitary facilities.
- Barricade / temporary enclosures / temporary protection / dust barriers / road closures.
- Patching, repair work, welding, and refurbishing by others.
- Concrete pour back, in-fill.
- Removal of CMU walls.
- Roof demolition. Removal of main trunk lines and RTUs / AHUs.
- Remove furniture, equipment, safe, hood, appliances, workstations, and artwork.
- Shelving, fixtures, cabinetry, lockers, and such not shown in the drawings will be priced accordingly.
- Trash and/or debris left behind by previous tenant not shown in the drawings will be priced accordingly.
- Concrete x-ray / scanning by others. Markings & layouts by G.C.
- Asbestos abatement, asbestos survey, air monitoring, permit costs, sewer fee cost.
- Terminate cap & seal plumbing/sewer/gas lines. Electrical make safe.
- Core drilling, Saw-cut, trench & remove slab. Excavate dirt / soil. Shoring & bracing by G.C.
- Refrigerant to be drained by HVAC contractor prior to demolition.
- Grinding, sanding, bead blasting and/or using or removing chemicals/solvents/paints.
- Any element found above ceiling, under the flooring or behind walls not shown in the drawings will be subject to a change order.
- Utility work / disconnects / re-routes. Fire protection demolition & sprinkler work by others.
- Prepare shop drawings, rebar / bar-bending schedule, core samples, and mock-ups.
- This proposal excludes demolition/removal of hardwood flooring.

SPECIAL NOTES

- Night work is included in this offer.
- Proposal based on plans only, regardless of provided pictures.
- Disassemble Dynamic will be careful when performing the scope(s) of work listed above, however, is not responsible for any damages or disturbance to the ground, concrete slabs, sidewalks, foundations, irrigation, buildings, pavements, etc. caused by demolition & haul-off procedures.
- We acknowledge receipt of all addenda & supplemental notices for this project.
- Based on (1) mobilization. Disassemble Dynamic will charge $3,250.00 for every additional mobilization. This excludes the price of tools, machinery, and equipment.
- Disassemble Dynamic has the right to withdraw or modify this proposal, if not accepted in writing within 90 days of the above date.
- Disassemble Dynamic will charge for idle time lost. i.e., elevator malfunction, etc.
- Disassemble Dynamics will charge an additional amount if another disposal / waste management company is to be used. An allowance / change order will also be added if only 1 dumpster is allowed on the premises at a time or if the GC requires us to perform a ‘live load’.
- An allowance / change order will also be added if the dumpster location is farther than 150 yards from the building.
- Any other work requested shall be priced accordingly.

OUR OFFER

DESCRIPTION	USD

BASE BID	$ 12,600.00
Alternate: Concrete grinding and adhesive removal of exposed slab surfaces to provide a smooth substrate for new floor finishes following demolition activities.	$ 1,500.00
TOTAL	**$ 14,100.00**

PAYMENT TERMS

- Payment in full shall be made within thirty (30) days of completion.
- Taxes are not included in this proposal. Bonding is excluded.
- Quote is based on zero (0) retainage being withheld. All unpaid invoices shall carry interest in the rate of 2.5% per month until the balance is paid in full. In the event of any outstanding amount that must be collected by an attorney, the customer shall be liable for attorney's fees and costs of litigation. If payment is not received within 45 days from completion of job, a lien will be placed on the property.
- The party accepting this offer agrees that any dispute or conflict that arises from the contents of this bid, agreement or contract between the parties shall be heard in district court in Bexar County, Texas.

If you have any queries, please do not hesitate to contact the undersigned.

Best regards,

Shawn Ziegaus

3325 US-441 #101 • Lake City, FL, USA 32025 • Mob 386.365.7886 • E-Mail shawn@disassembledynamics.com